



PURCHASING

ADDENDUM 2

Date: 4/30/2021

IFB #2021-2-65 Alma Drive and Ridgeview Drive Roadway Improvements

The following items take precedence over the initial bid specifications, where supplemented here. The original requirements, not affected by this addendum, shall remain in effect.

Two (2) new attachments are available in the E-bidding System providing a revised bidder proposal:

1. Bidders Proposal (pdf form)
2. Bidders Proposal (excel fillable form)

Please use this revised form for bid submittals.

PLEASE RETURN 1 SIGNED COPY OF THIS ADDENDUM WITH YOUR PROPOSAL

Signature of Officer

Date

ALMA DRIVE AND RIDGEVIEW DRIVE ROADWAY IMPROVEMENTS
BID# 2021-02-65 CIP# ST2004

PAVING AND DRAINAGE

ITEM NO.	EST QNTY	UNIT	DESCRIPTION AND PRICE IN WORDS	UNIT PRICE IN FIGURES	EXTENDED AMOUNT
1	1	LS	For mobilization and move-in complete and in place including ROW preparations, bonds, insurance, and permitting for the Lump Sum of _____ Dollars & _____ Cents		\$0.00
2	2	EA	Implement project signs along with all other incidentals necessary _____ Dollars & _____ Cents per Each		\$0.00
3	1	LS	SWPP and all incidentals for the Lump Sum of _____ Dollars & _____ Cents		\$0.00
4	1	LS	Erosion Control for all disturbed areas, including inlet sediment barriers, maintenance, and all incidentals for the Lump Sum of _____ Dollars & _____ Cents		\$0.00
5	1	LS	Implement traffic control, signing, barricading, arrow boards, and message boards along with all other incidentals necessary for the Lump Sum of _____ Dollars & _____ Cents		\$0.00
6	8,000	CY	Unclassified roadway excavation including all clearing and hauling surplus material to nearby site for the sum of _____ Dollars & _____ Cents per Cubic Yard		\$0.00
7	18,082	SY	Pulverizing, mixing and compacting 6 inch thick lime subgrade compacted to 95% proctor density 1 foot past curb for the sum of _____ Dollars & _____ Cents per Square Yard		\$0.00
8	362	TONS	Hydrated Lime for subgrade treatment all according to the plans and specifications, complete and in place for the sum of _____ Dollars & _____ Cents per Ton		\$0.00
9	17,065	SY	Construct 9 inch Class C, 3600 psi, reinforced concrete street paving including curb and gutter, longitudinal joint cuts, and all incidentals for the sum of _____ Dollars & _____ Cents per Square Yard		\$0.00
10	1,112	SY	Sawcut, remove, and dispose of reinforced concrete flatwork including concrete street pavement, concrete sidewalk, ramps and all incidentals for the sum of _____ Dollars & _____ Cents per Square Yard		\$0.00

ALMA DRIVE AND RIDGEVIEW DRIVE ROADWAY IMPROVEMENTS
BID# 2021-02-65 CIP# ST2004

ITEM NO.	EST QNTY	UNIT	DESCRIPTION AND PRICE IN WORDS	UNIT PRICE IN FIGURES	EXTENDED AMOUNT
11	141	SY	Construct 4 inch Class C, 3600 psi, reinforced concrete sidewalk paving, including all incidentals for the sum of _____ Dollars & _____ Cents per Square Yard		\$0.00
12	5	EA	Construct 4 inch Class C, 3600 psi, reinforced concrete type G barrier free ramp, including truncated domed pavers and all incidentals for the sum of _____ Dollars & _____ Cents per Each		\$0.00
13	4	EA	Construct 6 inch Class C, 3600 psi, reinforced concrete wide trail barrier free ramp, including truncated domed pavers and all incidentals for the sum of _____ Dollars & _____ Cents per Each		\$0.00
14	732	LF	Sawcut, remove, and dispose of existing reinforced concrete curb and gutter including all incidentals for the sum of _____ Dollars & _____ Cents per Linear Foot		\$0.00
15	1	EA	Relocate existing fire hydrants including all incidentals for the sum of _____ Dollars & _____ Cents per Each		\$0.00
16	1,872	LF	Furnish and install 18 inch Class III RCP storm sewer pipe in variable depth trench, including all Wye Connections & fittings and all incidentals for the sum of _____ Dollars & _____ Cents per Linear Foot		\$0.00
17	1,091	LF	Furnish and install 21 inch Class III RCP storm sewer pipe in variable depth trench, including all Wye Connections & fittings and all incidentals for the sum of _____ Dollars & _____ Cents per Linear Foot		\$0.00
18	107	LF	Furnish and install 21 inch Class IV RCP storm sewer pipe in variable depth trench, including all Wye Connections & fittings and all incidentals for the sum of _____ Dollars & _____ Cents per Linear Foot		\$0.00
19	530	LF	Furnish and install 24 inch Class III RCP storm sewer pipe in variable depth trench, including all Wye Connections & fittings and all incidentals for the sum of _____ Dollars & _____ Cents per Linear Foot		\$0.00
20	326	LF	Furnish and install 27 inch Class III RCP storm sewer pipe in variable depth trench, including all Wye Connections & fittings and all incidentals for the sum of _____ Dollars & _____ Cents per Linear Foot		\$0.00

**ALMA DRIVE AND RIDGEVIEW DRIVE ROADWAY IMPROVEMENTS
 BID# 2021-02-65 CIP# ST2004**

ITEM NO.	EST QNTY	UNIT	DESCRIPTION AND PRICE IN WORDS	UNIT PRICE IN FIGURES	EXTENDED AMOUNT
21	441	LF	Furnish and install 30 inch Class III RCP storm sewer pipe in variable depth trench, including all Wye Connections & fittings and all incidentals for the sum of _____ Dollars & _____ Cents per Linear Foot		\$0.00
22	3	EA	Furnish and install concrete collar including all incidentals for the sum of _____ Dollars & _____ Cents per Each		\$0.00
23	1	EA	Furnish and install 3x3 foot Storm sewer manhole, including all incidentals for the sum of _____ Dollars & _____ Cents per Each		\$0.00
24	1	EA	Furnish and install 4x4 foot Storm sewer manhole, including all incidentals for the sum of _____ Dollars & _____ Cents per Each		\$0.00
25	1	EA	Furnish and install 5x5 foot Storm sewer manhole, including all incidentals for the sum of _____ Dollars & _____ Cents per Each		\$0.00
26	1	EA	Furnish and install connection to existing 18 inch RCP pipe including all incidentals for the sum of _____ Dollars & _____ Cents per Each		\$0.00
27	2	EA	Furnish and install connection to existing 21 inch RCP pipe including all incidentals for the sum of _____ Dollars & _____ Cents per Each		\$0.00
28	4	EA	Furnish and install connection to existing 8'X5' foot RCB pipe including all incidentals for the sum of _____ Dollars & _____ Cents per Each		\$0.00
29	15	EA	Construct 20 foot, concrete recessed curb inlet including all excavation, reinforcement, backfilling and all other incidentals for the sum of _____ Dollars & _____ Cents per Each		\$0.00
30	3	EA	Construct TXDOT Type 1 curb and grate inlet for the sum of _____ Dollars & _____ Cents per Each		\$0.00

**ALMA DRIVE AND RIDGEVIEW DRIVE ROADWAY IMPROVEMENTS
 BID# 2021-02-65 CIP# ST2004**

ITEM NO.	EST QNTY	UNIT	DESCRIPTION AND PRICE IN WORDS	UNIT PRICE IN FIGURES	EXTENDED AMOUNT
31	1	EA	Lower 8" water main to maintain 2' separation including all incidentals for the sum of _____ Dollars & _____ Cents per Each		\$0.00
32	4,367	LF	Furnish and install complete trench safety for storm sewer installations including all incidentals for the sum of _____ Dollars & _____ Cents per Linear Foot		\$0.00
33	4,367	LF	Post Construction TV inspection for storm Sewer Installation including all incidentals for the sum of _____ Dollars & _____ Cents per Linear Foot		\$0.00
34	3,215	SF	Furnish and install brick pavers including all incidentals for the sum of _____ Dollars & _____ Cents per Square Foot		\$0.00
35	16,500	SY	Furnish and install block sodding, including 4 inches of top soil and watering until established, including all incidentals for the sum of _____ Dollars & _____ Cents per Square Yard		\$0.00
36	14,604	LF	Furnish and install 4" thermoplastic white skip lane striping including refresh and any prep. work, complete and in place, for the sum of _____ Dollars & _____ Cents per Linear Foot		\$0.00
37	5,165	LF	Furnish and install 8" thermoplastic white solid lane striping including refresh and any prep. work, complete and in place, for the sum of _____ Dollars & _____ Cents per Linear Foot		\$0.00
38	632	LF	Furnish and install 8" thermoplastic white dotted (right only lanes) striping including refresh and any prep for the sum of _____ Dollars & _____ Cents per Linear Foot		\$0.00
39	1,192	LF	Furnish and install pre-formed pavement white 4" edge striping including refresh and any prep. work, complete and in place, for the sum of _____ Dollars & _____ Cents per Linear Foot		\$0.00
40	100	LF	Furnish and install 4" thermoplastic yellow edge striping including refresh and any prep. work, complete and in place, for the sum of _____ Dollars & _____ Cents per Linear Foot		\$0.00
41	422	LF	Furnish and install 12" thermoplastic white crosswalk traverse striping including refresh and any prep. work, complete and in place, for the sum of _____ Dollars & _____ Cents per Linear Foot		\$0.00

**ALMA DRIVE AND RIDGEVIEW DRIVE ROADWAY IMPROVEMENTS
 BID# 2021-02-65 CIP# ST2004**

ITEM NO.	EST QNTY	UNIT	DESCRIPTION AND PRICE IN WORDS	UNIT PRICE IN FIGURES	EXTENDED AMOUNT
42	908	LF	Furnish and install 12" thermoplastic white crosswalk longitudinal striping including refresh and any prep. work, complete and in place, for the sum of _____ Dollars & _____ Cents per Linear Foot		\$0.00
43	2,208	LF	Furnish and install 12" thermoplastic white chevron striping including refresh and any prep. work, complete and in place, for the sum of _____ Dollars & _____ Cents per Linear Foot		\$0.00
44	516	LF	Furnish and install 2' thermoplastic white stop bar striping including refresh and any prep. work, complete and in place, for the sum of _____ Dollars & _____ Cents per Linear Foot		\$0.00
45	22	EA	Furnish and install thermoplastic white directional arrows striping including refresh and any prep. work, complete and in place, for the sum of _____ Dollars & _____ Cents per Each		\$0.00
46	2	EA	Furnish and install thermoplastic white yield markings 3' wide (6 triangles) including any prep. work, complete and in place, for the sum of _____ Dollars & _____ Cents per Each		\$0.00
47	7	EA	Relocate signage called out per plans including all incidentals for the sum of _____ Dollars & _____ Cents		\$0.00
48	1	EA	Remove and dipose of existing drop inlet for the sum of _____ Dollars & _____ Cents per Each		\$0.00

TOTAL BASE BID: \$0.00

Calendar Days

ALMA DRIVE AND RIDGEVIEW DRIVE ROADWAY IMPROVEMENTS
BID# 2021-02-65 CIP# ST2004

PAVING AND DRAINAGE

ITEM NO.	EST QNTY	UNIT	DESCRIPTION AND PRICE IN WORDS	UNIT PRICE IN FIGURES	EXTENDED AMOUNT
A1-1	1	LS	Erosion Control for all disturbed areas, including inlet sediment barriers, maintenance and all incidentals for the Lump Sum of _____ Dollars & _____ Cents		\$0.00
A1-2	3,000	CY	Unclassified roadway excavation including all clearing, hauling and disposal of surplus for the sum of _____ Dollars & _____ Cents per Cubic Yard		\$0.00
A1-3	5,321	SY	Pulverizing, mixing and compacting 6 inch thick lime subgrade compacted to 95% proctor density for the sum of _____ Dollars & _____ Cents per Square Yard		\$0.00
A1-4	106	TONS	Hydrated Lime for subgrade treatment all according to the plans and specifications, complete and in place for the sum of _____ Dollars & _____ Cents per Ton		\$0.00
A1-5	4,985	SY	Construct 9 inch Class C, 3600 psi, reinforced concrete street paving with reinforced curb and gutter, including all incidentals for the sum of _____ Dollars & _____ Cents per Square Yard		\$0.00
A1-6	1,953	LF	Sawcut, remove, and dispose of existing reinforced concrete curb and gutter including all incidentals for the sum of _____ Dollars & _____ Cents per Linear Foot		\$0.00
A1-7	997	LF	Furnish and install pre-formed pavement white 8" dotted (right only lanes) striping including all incidentals for the lump sum of _____ Dollars & _____ Cents per Linear Foot		\$0.00
A1-8	2,357	LF	Furnish and install pre-formed pavement solid white 8" lane striping including all incidentals for the lump sum of _____ Dollars & _____ Cents per Linear Foot		\$0.00
A1-9	187	LF	Furnish and install pre-formed pavement white 12" chevron striping including all incidentals for the lump sum of _____ Dollars & _____ Cents per Linear Foot		\$0.00
A1-10	16	EA	Furnish and install pre-formed pavement white directional arrows striping including all incidentals for the sum of _____ Dollars & _____ Cents per Each		\$0.00

TOTAL ALTERNATE 1:

\$0.00

Calendar Days

ALMA DRIVE AND RIDGEVIEW DRIVE ROADWAY IMPROVEMENTS
BID# 2021-02-65 CIP# ST2004

ILLUMINATION

ITEM NO.	EST QNTY	UNIT	DESCRIPTION AND PRICE IN WORDS	UNIT PRICE IN FIGURES	EXTENDED AMOUNT
A2-1	2,115	LF	CONDUIT (PVC) (SCHD 40) (2") TRENCH, furnish and install complete in place for the sum of _____ Dollars & _____ Cents per Linear Foot		\$0.00
A2-2	134	LF	CONDUIT (PVC) (SCHD 40) (2") BORE, furnish and install complete in place for the sum of _____ Dollars & _____ Cents per Linear Foot		\$0.00
A2-3	2,370	LF	ELEC CONDUCTOR (NO 8) BARE, furnish and install complete in place for the sum of _____ Dollars & _____ Cents per Linear Foot		\$0.00
A2-4	4,740	LF	ELEC CONDUCTOR (NO 8) INSULATED, furnish and install complete in place for the sum of _____ Dollars & _____ Cents per Linear Foot		\$0.00
A2-5	12	EA	ILLUMINATION POLE - TWIN (City Standard), furnish and install complete in place for the sum of _____ Dollars & _____ Cents Each		\$0.00
A2-6	24	EA	LUMINARIE FIXTURE - 135W LED, furnish and install complete in place for the sum of _____ Dollars & _____ Cents Each		\$0.00
A2-7	60	LF	DRILL SHAFT (RDWY ILL POLE) (24 IN) (City Standard), complete in place for the sum of _____ Dollars & _____ Cents per Linear Foot		\$0.00

TOTAL ALTERNATE 2: \$0.00

Calendar Days

**EAST BETHANY DR HERITAGE PARKWAY
TRAFFIC SIGNAL CONSTRUCTION
BID# 2019-7-71 CIP# ST 1907**

ALMA DR. AT RIDGEVIEW DR. TRAFFIC SIGNAL - SIGNAL ITEMS

ITEM NO.	EST QNTY	UNIT	DESCRIPTION AND PRICE IN WORDS	UNIT PRICE IN FIGURES	EXTENDED AMOUNT
A3-1	2	EA	Remove existing ground box, including all incidentals for the sum of _____ Dollars & _____ Cents per Each		\$0.00
A3-2	1	EA	Remove, salvage, and return to City, existing traffic signal heads, cameras ,traffic signal cables, traffic signal cabinet including all incidentals for the sum of _____ Dollars & _____ Cents per Each		\$0.00
A3-3	1	EA	Install highway traffic system, including cabinets & base, cameras, radio, opticom, cables, conductors, conduit, push buttons, poles, signs and all additional incidentals for the sum of _____ Dollars & _____ Cents per Each		\$0.00
A3-4	130	LF	Furnish and install 2 inch Schedule 40 PVC conduit, including all incidentals for the sum of _____ Dollars & _____ Cents per Linear Foot		\$0.00
A3-5	60	LF	Furnish and install 3 inch Schedule 40 PVC conduit, including all incidentals for the sum of _____ Dollars & _____ Cents per Linear Foot		\$0.00
A3-6	550	LF	Furnish and install 4 inch Schedule 40 PVC conduit, by other than open cut, including all incidentals for the sum of _____ Dollars & _____ Cents per Linear Foot		\$0.00
A3-7	1,125	LF	Furnish and install No. 6 (bare) electrical conductors, including all incidentals for the sum of _____ Dollars & _____ Cents per Linear Foot		\$0.00
A3-8	2,290	LF	Furnish and install Type A, 14 AWG, 3 conductor traffic signal cable, including all incidentals for the sum of _____ Dollars & _____ Cents per Linear Foot		\$0.00
A3-9	720	LF	Furnish and install Type A, 14 AWG, 5 conductor traffic signal cable, including all incidentals for the sum of _____ Dollars & _____ Cents per Linear Foot		\$0.00
A3-10	330	LF	Furnish and install Type A, 14 AWG, 7 conductor traffic signal cable, including all incidentals for the sum of _____ Dollars & _____ Cents per Linear Foot		\$0.00

**EAST BETHANY DR HERITAGE PARKWAY
TRAFFIC SIGNAL CONSTRUCTION
BID# 2019-7-71 CIP# ST 1907**

ALMA DR. AT RIDGEVIEW DR. TRAFFIC SIGNAL - SIGNAL ITEMS

ITEM NO.	EST QNTY	UNIT	DESCRIPTION AND PRICE IN WORDS	UNIT PRICE IN FIGURES	EXTENDED AMOUNT
A3-11	1,155	LF	Furnish and install Type A, 14 AWG, 10 conductor traffic signal cable, including all incidentals for the sum of _____ Dollars & _____ Cents per Linear Foot		\$0.00
A3-12	1,100	LF	Furnish and install Type A, 14 AWG, 25 conductor traffic signal cable, including all incidentals for the sum of _____ Dollars & _____ Cents per Linear Foot		\$0.00
A3-13	1,430	LF	Furnish and install Opticom cable, including all incidentals for the sum of _____ Dollars & _____ Cents per Each		\$0.00
A3-13	1	EA	Furnish and install Type C ground box with apron, including all incidentals for the sum of _____ Dollars & _____ Cents per Each		\$0.00
A3-14	1	EA	Furnish and install Type B ground box with apron, including all incidentals for the sum of _____ Dollars & _____ Cents per Each		\$0.00
A3-15	3	EA	Furnish and install 12 inch LED (Green) vehicle signal section, including all incidentals for the sum of _____ Dollars & _____ Cents per Each		\$0.00
A3-16	4	EA	Furnish and install 12 inch LED (Green Arrow) vehicle signal section, including all incidentals for the sum of _____ Dollars & _____ Cents per Each		\$0.00
A3-17	3	EA	Furnish and install 12 inch LED (Yellow) vehicle signal section, including all incidentals for the sum of _____ Dollars & _____ Cents per Each		\$0.00
A3-18	8	EA	Furnish and install 12 inch LED (Yellow Arrow) vehicle signal section, including all incidentals for the sum of _____ Dollars & _____ Cents per Each		\$0.00
A3-19	3	EA	Furnish and install 12 inch LED (Red) vehicle signal section, including all incidentals for the sum of _____ Dollars & _____ Cents per Each		\$0.00
A3-20	8	EA	Furnish and install 12 inch LED (Red Arrow) vehicle signal section, including all incidentals for the sum of _____ Dollars & _____ Cents per Each		\$0.00

**EAST BETHANY DR HERITAGE PARKWAY
TRAFFIC SIGNAL CONSTRUCTION
BID# 2019-7-71 CIP# ST 1907**

ALMA DR. AT RIDGEVIEW DR. TRAFFIC SIGNAL - SIGNAL ITEMS

ITEM NO.	EST QNTY	UNIT	DESCRIPTION AND PRICE IN WORDS	UNIT PRICE IN FIGURES	EXTENDED AMOUNT
A3-21	8	EA	Furnish and install LED (Countdown) pedestrian signal section, including all incidentals for the sum of _____ Dollars & _____ Cents per Each		\$0.00
A3-22	3	EA	Furnish and install 12 inch - 3 Section Poly back plate, including all incidentals for the sum of _____ Dollars & _____ Cents per Each		\$0.00
A3-23	4	EA	Furnish and install 12 inch - 5 Section Poly back plate, including all incidentals for the sum of _____ Dollars & _____ Cents per Each		\$0.00
A3-24	4	EA	Furnish and install push Button station, including all incidentals for the sum of _____ Dollars & _____ Cents per Each		\$0.00
A3-25	2	EA	Furnish and install pedestal pole assembly including all incidentals for the sum of _____ Dollars & _____ Cents per Each		\$0.00

TOTAL ALTERNATE 3

\$0.00

Calendar Days

**EAST BETHANY DR HERITAGE PARKWAY
TRAFFIC SIGNAL CONSTRUCTION
BID# 2019-7-71 CIP# ST 1907**

ALMA DR. AT EXCHANGE PKWY. RIGHT TURN LANE

ITEM NO.	EST QNTY	UNIT	DESCRIPTION AND PRICE IN WORDS	UNIT PRICE IN FIGURES	EXTENDED AMOUNT
A4-1	1	LS	All Traffic Control Measures, including, but not limited to, construction sequencing, barricading, traffic control design, panels, signs, and temporary pavement markings, complete in place, including all incidentals for the Lump Sum of _____ Dollars & _____ Cents		\$0.00
A4-2	1	LS	Erosion Control for all disturbed areas, including inlet sediment barriers, maintenance and all incidentals for the Lump Sum of _____ Dollars & _____ Cents		\$0.00
A4-3	1	LS	Irrigation System Adjustments, complete in place and all additional incidentals for the Lump Sum of _____ Dollars & _____ Cents		\$0.00
A4-4	240	SY	Sawcut, Remove and Dispose of Existing Concrete Flatwork (Sidewalk, BFR, Bricks, etc.), including all incidentals for the sum of _____ Dollars & _____ Cents per Square Yard		\$0.00
A4-5	375	LF	Sawcut, Remove and Dispose of Existing Concrete Curb and Gutter, including all incidentals for the sum of _____ Dollars & _____ Cents per Linear Foot		\$0.00
A4-6	1	EA	Relocate Existing Pedestrian Traffic Signal Pole, including all appurtenances, complete in place for the sum of _____ Dollars & _____ Cents per Each		\$0.00
A4-7	1	LS	Relocate Existing Fire Hydrant, including riser pipe, 6" C900 PVC pipe, thrust blocking, and all appurtenances, complete in place, including all incidentals for the Lump Sum of _____ Dollars & _____ Cents		\$0.00
A4-8	1	EA	Remove Existing Road Signs, return sign to City of Allen Traffic Dept., including all incidentals for the sum of _____ Dollars & _____ Cents per Each		\$0.00
A4-9	2	EA	Adjust Existing Water Valve Riser and Cover to Final Grade, including all incidentals for the sum of _____ Dollars & _____ Cents per Each		\$0.00
A4-10	1	EA	Remove Existing Traffic Control Box, including all incidentals for the sum of _____ Dollars & _____ Cents per Each		\$0.00
A4-11	35	SF	Remove and Salvage Existing Paving Stones and Dispose of Concrete Base, including all incidentals for the sum of _____ Dollars & _____ Cents per Square Foot		\$0.00

**EAST BETHANY DR HERITAGE PARKWAY
TRAFFIC SIGNAL CONSTRUCTION
BID# 2019-7-71 CIP# ST 1907**

ALMA DR. AT EXCHANGE PKWY. RIGHT TURN LANE

ITEM NO.	EST QNTY	UNIT	DESCRIPTION AND PRICE IN WORDS	UNIT PRICE IN FIGURES	EXTENDED AMOUNT
A4-12	350	CY	Unclassified Street Excavation, including all incidentals for the sum of _____ Dollars & _____ Cents per Cubic Yard		\$0.00
A4-13	415	SY	Construct 9 inch Class C, 3600 psi, reinforced concrete street paving including curb and gutter, including all incidentals for the sum of _____ Dollars & _____ Cents per Square Yard		\$0.00
A4-14	40	SY	Construct 6" 3600 PSI (Class 'C') Reinforced Concrete Trail Pavement, including all incidentals for the sum of _____ Dollars & _____ Cents per Square Yard		\$0.00
A4-15	160	SY	Construct 4" 3600 PSI (Class 'C') Reinforced Concrete Sidewalk Pavement, including all incidentals for the sum of _____ Dollars & _____ Cents per Square Yard		\$0.00
A4-16	390	LF	Longitudinal Butt Joint, complete in place, including all incidentals for the sum of _____ Dollars & _____ Cents per Linear Foot		\$0.00
A4-17	455	SY	Construct 6" Thick Cement Stabilized Subgrade (6%), including placement, mixing, and compaction, complete in place, including all incidentals for the sum of _____ Dollars & _____ Cents per Square Yard		\$0.00
A4-18	8	TON	Furnish Cement, complete in place, including all incidentals for the sum of _____ Dollars & _____ Cents per Ton		\$0.00
A4-19	1	EA	Construct TxDOT STD. Barrier Free Ramp Type 1 (10' wide), including all incidentals for the sum of _____ Dollars & _____ Cents per Each		\$0.00
A4-20	900	SY	Furnish and Place Block Sodding (Bermuda), including 4" topsoil, watering and fertilizer until established for the sum of _____ Dollars & _____ Cents per Square Yard		\$0.00
A4-21	200	LF	Furnish and Install 8" White Thermoplastic Solid Stripe, including any prep. work, complete and in place for the sum of _____ Dollars & _____ Cents per Linear Foot		\$0.00
A4-22	40	LF	Furnish and Install 12" White Thermoplastic Solid Crosswalk Stripe including any prep. work, complete and in place for the sum of _____ Dollars & _____ Cents per Linear Foot		\$0.00

**EAST BETHANY DR HERITAGE PARKWAY
TRAFFIC SIGNAL CONSTRUCTION
BID# 2019-7-71 CIP# ST 1907**

ALMA DR. AT EXCHANGE PKWY. RIGHT TURN LANE

ITEM NO.	EST QNTY	UNIT	DESCRIPTION AND PRICE IN WORDS	UNIT PRICE IN FIGURES	EXTENDED AMOUNT
A4-23	20	LF	Furnish and Install 24" White Thermoplastic Solid Stop Bar, including any prep. work, complete and in place for the sum of _____ Dollars & _____ Cents per Linear Foot		\$0.00
A4-24	2	EA	Furnish and Install White Thermoplastic Pavement Markings (Arrows) (Words), including any prep. work, complete and in place for the sum of _____ Dollars & _____ Cents per Each		\$0.00
A4-25	1	EA	Install traffic signs, including post and foundation, including all incidentals for the sum of _____ Dollars & _____ Cents per Each		\$0.00

TOTAL ALTERNATE 4

\$0.00

Calendar Days

PROPOSAL SUMMARY

TOTAL BASE BID	<u>\$0.00</u>	0
TOTAL ALTERNATE #1	<u>\$0.00</u>	0
TOTAL ALTERNATE #2	<u>\$0.00</u>	0
TOTAL ALTERNATE #3	<u>\$0.00</u>	0
TOTAL ALTERNATE #4	<u>\$0.00</u>	0

<u>CALENDAR DAYS BASE BID:</u>	<u>0</u>	0
<u>CALENDAR DAYS ALTERNATE BID #1:</u>	<u>0</u>	0
<u>CALENDAR DAYS ALTERNATE BID #2:</u>	<u>0</u>	0
<u>CALENDAR DAYS ALTERNATE BID #3:</u>	<u>0</u>	0
<u>CALENDAR DAYS ALTERNATE BID #4:</u>	<u>0</u>	0

<u>TOTAL BID</u>	<u>\$0.00</u>
<u>TOTAL BID + ALTERNATE #1</u>	<u>\$0.00</u>
<u>TOTAL BID + ALTERNATE #2</u>	<u>\$0.00</u>
<u>TOTAL BID + ALTERNATE #3</u>	<u>\$0.00</u>
<u>TOTAL BID + ALTERNATE #4</u>	<u>\$0.00</u>
<u>TOTAL BID + ALTERNATE #1-4</u>	<u>\$0.00</u>

The City of Allen reserves the right to award the base bid and any combination of alternates by signing the Bid Endorsement and Standard Form of Agreement.

